

WATER TUNNEL

Technical Characteristics:

Test Section: 50 x 50 cm

Test Section Length: 500 cm

• Range Fluid Speed: 0 – 0.75 m/s

• Contraction ratio: 14:1

• Max. flow rate: 650 m³/h.

• Power: 48 kW



Instrumentation:

Magnetic flow meter with resolution < 0,5 % f.e.

Traversing system along the tunnel for visualization with high speed cameras Stereo PIV system able to measure the 3 velocity components in any location

of the tunnel working section



